

John A Stone PE, PLS
Jon W Earnest PLS
David J Connor



Roads & Bridges
Streets & Storm Sewers
Sanitary Sewers
Waste Water Treatment
Public Water Supplies
Water Towers / Wells
Funding Solicitation
Land Surveys
Industrial Layout
Drainage
Subdivisions

Phone: (618) 544-8623
Fax: (618) 544-3012

210 East Locust Street - P.O. Box 618 - Robinson, IL 62454
www.connorengineers.com

DATE: JUNE 24, 2011

PROJECT: EATON WATER DISTRICT - NORTHEAST RURAL EXTENSION

RE: ADDENDUM #1

THE FOLLOWING SHALL BE ADDED TO THE CONTRACT DOCUMENTS:

TECHNICAL SPECIFICATIONS / WATER TOWER DISMANTLING

A. GENERAL

Unless otherwise shown on the PROJECT PLANS, or as specified herein, all construction methods shall be in accordance with applicable industry standards, and in strict accordance with all applicable safety regulations. The water tower to be dismantled stands in Annapolis, Illinois.

B. DISMANTLING OF TOWER STRUCTURE

Precaution shall be taken when the dismantling process occurs. The CONTRACTOR shall be responsible for all local, state and federal regulations pertaining to air pollution and land pollution control. The CONTRACTOR shall take special precautions to protect existing structures and items located around the perimeter of the tank. The structures and items are considered to be buildings, generators, water salesman, etc.

The CONTRACTOR shall provide a tarp type cover to be laid around the dismantling site area. This tarp shall be used to catch falling contaminated material. The CONTRACTOR shall make good faith efforts to assure the tarp material remains stretched out. The tarp shall lie completely under the tower, and extend a minimum of 15' outside the foundations of the tower. The OWNER will assume the responsibility of site clean-up pertaining to contamination, if any. The CONTRACTOR shall leave the site in a "broom clean" condition.

The coating of the exterior of the structure contains a lead content. The CONTRACTOR, as a result of this project, will assume ownership of the lead contaminated materials.

The CONTRACTOR is not responsible for removing the concrete foundations.

C. REMOVAL OF EXISTING ATTACHMENTS

There are currently antenna type attachments in various location on the tower structure. These items shall be removed and neatly placed on adjacent OWNER property. Unless otherwise in use, any coaxial lines will not be salvaged.

D. CLEANUP OF SURFACE

The CONTRACTOR shall be responsible for removing all debris from the project site upon completion of the project. All materials shall be removed in a manner that a lawn mower will not collect objects. The OWNER will assume the responsibility of site clean-up pertaining to soil contamination, if any. The CONTRACTOR shall leave the site in a "broom clean" condition.

E. BASIS OF PAYMENT

The WATER TOWER DISMANTLING shall be paid for at the lump sum unit bid price, as removed. Payment of such shall include, but not be limited to the following:

1. Containment Procedures (Tarps)
2. Tank Dismantling
3. Tank Disposal
4. Acquisition of Additional Easement, If Necessary
5. Site Cleanup ("Broom Clean")

SHANNON WOODARD, CONSULTANT